



NOTES:

1. TRENCH EXCAVATION PER ISPMC SECTION 301.
2. PIPE BEDDING PER ISPMC SECTION 305.
3. BACKFILL AND COMPACTION PER ISPMC SECTION 306.
4. REFER TO ISPMC SECTION 304 FOR ADDITIONAL INFORMATION ON TRENCH FOUNDATION STABILIZATION IF NECESSARY FOR PROJECT CONSTRUCTION.
5. STREET CUTS AND SURFACE REPAIRS PER ISPMC SECTION 307 UNLESS OTHERWISE SHOWN IN THIS DETAIL.
6. ASPHALT CUTS AND PATCHES WILL NOT BE ALLOWED WITHIN THE WHEEL PATHS AND ALL CORNERS SHALL BE STRAIGHT CUTS (NOT RADIUS) UNLESS PRIOR WRITTEN APPROVAL FROM THE CITY OF McCALL PUBLIC WORKS DEPARTMENT HAS BEEN GRANTED.
7. ALL WORKMANSHIP LOCATED WITHIN A CITY OF McCALL RIGHT-OF-WAY TO CARRY A 2-YEAR WARRANTY.



PUBLIC WORKS DEPARTMENT
 815 N. SAMSON TRAIL
 McCALL, IDAHO 83638
 208.634.5580

CITY OF McCALL
TYPICAL TRENCH AND ASPHALT SURFACE REPAIR

STANDARD DRAWING NO.

MSD-302

PROJECT	DRAWN BY	SHEET NO.
DATE	2/15/2023	1 OF 1