

NOTES:

- 1. ALL MATERIALS AND CONSTRUCTION SHALL BE PER ISPWC SPECIFICATIONS.
- 2. CURB AND GUTTER CONCRETE MIX DESIGN TO BE CLASS 4000A WITH 3/4" AGGREGATE IN ACCORDANCE WITH ISPWC SECTION 703, CAST-IN-PLACE CONCRETE, TABLE 1. ALL OTHER CONCRETE (I.E. SIDEWALK, APPROACHES AND RAMPS) TO BE CLASS 4000B WITH 3/4" AGGREGATE IN ACCORDANCE WITH ISPWC SECTION 703, CAST-IN-PLACE CONCRETE, TABLE 1.
- 3. MICRO-SYNTHETIC FIBERS SHALL BE FIBERMESH OR APPROVED EQUIVALENT. LENGTH OF FIBERS SHALL BE AS RECOMMENDED BY THE MANUFACTURER. ADD 1.5 POUNDS OF FIBERMESH OR APPROVED EQUIVALENT PER CUBIC YARD OF CONCRETE, OR AS RECOMMENDED BY MANUFACTURER. REFER TO THE ITD AND ISPWC STANDARD DETAIL FOR ADDITIONAL INFORMATION PERTAINING TO CONCRETE REINFORCEMENT AND CONSTRUCTION JOINT/SCORE INTERVALS.
- 4. ALL CONCRETE FLATWORK SHALL NOT BE TROWELED; USE SCREED, FLOAT AND BROOM.
- 5. ALL SIDEWALKS SHALL BE FIVE (5") INCHES THICK WITH A MINIMUM OF FOUR (4") INCHES OF COMPACTED 3/4" MINUS AGGREGATE BASE. COMPACT TO MIN. 95% OF STANDARD PROCTOR.
- 6. SCORE INTERVALS PERPENDICULAR TO CURB TO MATCH WIDTH OF SIDEWALK NOT TO EXCEED FIVE (5') FEET SPACING. SIDEWALKS GREATER THAN FIVE (5') FEET IN WIDTH TO BE SCORED AT HALF WIDTH PARALLEL TO CURB AS WELL.
- 7. ALL STANDARD URBAN APPROACH RAMPS AND FLARES SHALL CONFORM TO ISPWC SD-710, SD-710A, SD-710B, OR SD-710C AND HAVE MINIMUM CONCRETE THICKNESS OF SIX (6") INCHES AND MINIMUM COMPACTED AGGREGATE BASE OF FOUR (4") INCHES.
- 8. CONTRACTOR TO SEAL ALL CONCRETE WITH SILANE-40 CONCRETE SEALER PER MANUFACTURER'S RECOMMENDATION.
- 9. ALL CONCRETE WORK TO CARRY A 2-YEAR WARRANTY AGAINST SCALED OR SPALLED SURFACES IN EXCESS OF 5% OF SURFACE AREA PER 20 S.F. PER CITY OF McCALL STANDARDS.
- 10. ALL CONCRETE WORK TO CARRY A MINIMUM 2-YEAR WARRANTY AGAINST SCALED OR SPALLED SURFACES IN EXCESS OF 5% OF THE SURFACE AREA PER 20 S.F.
- 11. ALL WORKMANSHIP LOCATED WITHIN A CITY OF McCALL RIGHT-OF-WAY TO CARRY A 2-YEAR WARRANTY.



PUBLIC WORKS DEPARTMENT 815 N. SAMSON TRAIL McCALL, IDAHO 83638 208.634.5580

CITY OF McCALL SIDEWALK CURB AND GUTTER INSTALLATION

 PROJECT
 .
 DRAWN BY
 SHEET NO.

 DATE
 1/12/2023
 .
 1 OF 1

STANDARD DRAWING NO.

MSD-704