


NOTES:

1. COMPACTION AND TESTING FOR ALL AGGREGATE BASE/SUBBASE MATERIAL SHALL BE IN ACCORDANCE WITH ISPWC 802.
2. ASPHALT FOUR (4") INCHES IN THICKNESS SHALL BE PLACED IN TWO (2") INCH LIFTS. ASPHALT THREE (3") INCHES OR LESS SHALL BE PLACED IN A SINGLE LIFT.
3. GEOTEXTILE FABRIC TO EXTEND 2' MIN. BEYOND THE EDGE OF ASPHALT. ALL SEAMS TO OVERLAP 2' MIN.
4. COMPACTION AND TESTING FOR ALL HOT MIX ASPHALT SHALL BE IN ACCORDANCE WITH ISPWC SECTION 810 AND PROJECT PLANS AND SPECIFICATIONS.
5. REVEGETATE ALL DISTURBED AREAS WITH A CITY APPROVED GRASS MIXTURE OVER FOUR (4") INCHES OF TOPSOIL, PER APPROVED LANDSCAPING PLAN, OR AS INDICATED WITHIN THE PLANS.

 City of McCall PUBLIC WORKS	PUBLIC WORKS DEPARTMENT 815 N. SAMSON TRAIL McCALL, IDAHO 83638 208.634.5580	CITY OF McCALL TYPICAL ROADWAY SECTION - ARTERIAL RURAL		STANDARD DRAWING NO. MSD-801B
		PROJECT .	DRAWN BY .	
		DATE 6/21/2022		