



NOTES:

1. TRENCH EXCAVATION PER ISPWC SECTION 301.
2. PIPE BEDDING PER ISPWC SECTION 305.
3. BACKFILL AND COMPACTION PER ISPWC SECTION 306.
4. REFER TO ISPWC SECTION 304 FOR ADDITIONAL INFORMATION ON TRENCH FOUNDATION STABILIZATION IF NECESSARY FOR PROJECT CONSTRUCTION.
5. STREET CUTS AND SURFACE REPAIRS PER ISPWC SECTION 307 UNLESS OTHERWISE SHOWN IN THIS DETAIL.
6. ASPHALT CUTS AND PATCHES WILL NOT BE ALLOWED WITHIN THE WHEEL PATHS WITHOUT PRIOR WRITTEN APPROVAL FROM THE CITY OF McCALL PUBLIC WORKS DEPARTMENT.
7. ALL WORKMANSHIP LOCATED WITHIN A CITY OF McCALL RIGHT-OF-WAY TO CARRY A 2-YEAR WARRANTY.



PUBLIC WORKS DEPARTMENT
 815 N. SAMSON TRAIL
 McCALL, IDAHO 83638
 208.634.5580

CITY OF McCALL
TYPICAL TRENCH AND GRAVEL SURFACE REPAIR

STANDARD DRAWING NO.

MSD-303

PROJECT	DRAWN BY	SHEET NO.
DATE 11/15/2021		1 OF 1